



गुरु घासीदासविश्वविद्यालय, बिलासपुर छ.ग.
GURU GHASIDAS VISHWAVIDYALAYA, BILASPUR (C.G.)

केंद्रीय विश्वविद्यालय अधिनियम 2009 के अंतर्गतस्थापितविश्वविद्यालय
(A Central University established by the Central Universities Act, 2009)
Phone 07752-260207, fax 07752-260154 Website www.ggu.ac.in

No/ /Engg/2014

Bilaspur. Date. / /2014

NOTICE INVITING QUOTATIONS

Sealed quotations are invited from contractors/reputed fabricators, manufactures by speed post/registered post only for the Spacial reper work staff qtr.The sealed quotation will be received in the office of undersigned by 04:00 PM on 30 / 07/2014 and opened at 05:00 PM on the same day.

S. No.	Perticuler	Estimated Cost
01	Spacial reper work staff qtr	Rs 5.00 Lakh
Note	Scheduled item for civil works will be taken from DSR. 2007	

Terms and Conditions

1. Rate are inclusive of all taxes.
2. Time allowed for this work is one month.
3. Payment shall be deducted as applicable.
4. Income tax shall be deducted as applicable.
5. Quality of work shall be as per CPWD manual.
6. The information about quotation please contact with University Engineer in office at working hours.

CC.No. /Engg/2014

1. PA to Registrar, for information to Registrar.
2. Finance Officer, for information.
3. Registered contractor.
4. CSIT for upload in our website.
5. Notice Board.

University Engineer

Bilaspur Date / /2014

University Engineer

To,

The Registrar
Guru Ghasidas Vishwavidyalaya
Bilaspur (CG)

Sub: Your enquiry no. S.No. /Engg/2014 Bilaspur. Date / /2014

Percentage rates are being given as follows:

Spacial reper work staff qtr.

S.O.R ITEM NO	ITEM DESCRIPTION	QTY	UNIT	RATE	Total value
2.8	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
2.8.1	All kinds of soil	42.00	cum	103.00	4348.00
2.27	Supplying and filling in plinth with Local sand under floors including, watering, ramming consolidating and dressing complete.	51.50	cum	301.00	1527.00
5.1.2	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	5.66	Cum	3732.00	21123.00
5.9	Centring and shuttering including strutting, propping etc. and removal of form for :				
5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts.	5.00	sqm	238.40	1192
5.22	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
5.22.6	Thermo-Mechanically Treated bars.	500.00	Kg	42.70	21350
6.4	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in :				
6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	10.00	Cum	2350.00	23500.00
13.4	15 mm cement plaster on rough side of single or half brick wall of mix :				
13.	1:6 (1 cement : 6 coarse sand)	33.50	sqm	80.00	2680.00

13.4	12 mm cement plaster on rough side of single or half brick wall of mix :				
13.4.2	1:6 (1 cement : 6 coarse sand)	33.00	sqm	67.00	2211.00
10.5	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.				
13.47.1	New work (Two or more coats applied @ 1.43 ltr/ 10 sum. over and including base coat of water proofing cement paint applied @ 2.20 kg/ 10 sum).	403.52	sqm	60.1	24251.00
9.48	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. all complete.				
9.48.1	Fixed to steel windows by welding.	1000.00	kg	59.25	59250.00
4.1.5	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	82.25	cum	42.27	21350
13.62	Synthic enamel	33.00	sqm	51.3	1692
				Total	492911.00

Note: Rate should be quoted in appropriate column.

Seal and Signatures of the Firm

I/we have done myself/our self fully satisfied to read & examine the notice inviting quotation, general conditions contract, all specials conditions & specifications of work, applicable specifications, drawings, designs, applicable schedule of rates, descriptions, all the rules in respect of contract and all other contents in the notice and here by agreed for execution of the said specified work for the University Authority within the time period in accordance with that at the rate as quoted.

In figures.....

In words.....

Percent below/at par/above of Delhi Schedule of Rates.

Dated.....

Signatures of the Firm

Postal Address:

Witness:

Address:

Occupations: