



गुरु घासीदासविश्वविद्यालय, बिलासपुर छ.ग.  
**GURU GHASIDAS VISHWAVIDYALAYA, BILASPUR (C.G.)**

केंद्रीय विश्वविद्यालय अधिनियम 2009 के अंतर्गतस्थापितविश्वविद्यालय  
(A Central University established by the Central Universities Act, 2009 )  
Phone 07752-260207, fax 07752-260154 Website [www.ggu.ac.in](http://www.ggu.ac.in)

No/ 82 /Engg/2014

Bilaspur. Date. 24 / 01 /2014

## NOTICE INVITING QUOTATIONS

Sealed quotations are invited from contractors/reputed fabricators, manufactures by speed post/registered post only for the Construction of **Canteen shade Extention** The sealed quotation will be received in the office of undersigned by 04:00 PM on 03 / 02/2014 and opened at 05:00 PM on the same day.

S. No	Description of work	Estimated Cost
01	Construction of <b>Canteen shade Extention</b> as per attached schedule.	Rs 1.70 Lakh

### Terms and Conditions

1. Rate are inclusive of all taxes.
2. Time allowed for this work is one month.
3. Payment shall be deducted as applicable.
4. Income tax shall be deducted as applicable.
5. Quality of work shall be as per CPWD manual.
6. The information about quotation please contact with University Engineer in office at working hours.

CC.No. 83 /Engg/2014

1. PA to Registrar, for information to Registrar.
2. Finance Officer, for information.
3. Registered contractor.
4. CSIT for upload in our website.
5. Notice Board.

University Engineer  
Bilaspur Date 24 /01 /2014

Assistant Engineer

To,

The Registrar  
Guru Ghasidas Vishwavidyalaya  
Bilaspur (CG)

Sub: Your enquiry no. S.No. /Engg/2014 Bilaspur. Date / /2014

Percentage rates are being given as follows:-

Construction of Canteen shade Extention							
S. No.	D.S.R ITEM NO	ITEM DESCRIPTION	QTY	UNIT	RATE	Total value	Remark s
1	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :					
	4.1.5	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	1	cum			
	4.1.2	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.5	cum			
03	N.D.S. R.	Providing & Laying trapezoidal Profile sheet Asfollowing specification Pre painted galvanized thicknes 0.5mm coil input width1250mm,supply width 1050mm minimum, covered width 980mm,Pitch 196mm, creast hight 26mm minimum, creast width 26mm,Lip 10mm	90.0 0	sqm			

4	10.2	Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. complete					
	10.1 6.1	Hot finished welded type tubes	1200.00	Kg.			
5	2.8	Earth work in excavation by mechanical means (Hydraulic Excavator )/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.					
	2.8. 1	All kinds of soil TBB-04 P-01 MB- 01 P-25	5.00	cum			
	5.22	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.					
	5.22. 6	Thermo-Mechanically Treated bars.	60.00	Kg			

**Note: Rate should be quoted in appropriate column.**

## Seal and Signatures of the Firm

I/we have done myself/our self fully satisfied to read & examine the notice inviting quotation, general conditions contract, all specials conditions & specifications of work, applicable specifications, drawings, designs, applicable schedule of rates, descriptions, all the rules in respect of contract and all other contents in the notice and here by agreed for execution of the said specified work for the University Authority within the time period in accordance with that at the rate as quoted.

Dated.....

Signatures of the Firm

Postal Address: .....

Witness: .....

Address: .....

Occupations: .....