S. No.   91/Extension/UTM/Store/GGV/2020                    Bilaspur, Dated-12.03.2020

## Corrigendum regarding Schedule 1 of LTE Document

1. In schedule 1 of tender document at page 6 in status "Web and Application filter" for user Identity "Layer *" is mentioned which is to be read as "Layer 8".

2. Following specification regarding hardware of Firewall is also to be read as part of schedule 1 of tender document at page 6.

| Status | Services /Modules |
|---|---|
| Ports | 8x1 GbE Built-in Copper Ports and 2X 10 Gbe SFP+ Ports and Future expansion slot to provision 2X 40 G QSFP Port. |
| Firewall Throughput | Minimum 40 Gbps |
| IPS Throughput | Minimum 9 Gbps & Antivirus throughput: 6 Gbps |
| Concurrent Connections | 19 Million & 200000 new sessions per second |
| NGFW throughput | 6 Gbps (IPS + App Ctrl + Web Filter) |

By Order,

Assistant Registrar (Store)