



गुरु घासीदासविश्वविद्यालय, बिलासपुर छ.ग.
GURU GHASIDAS VISHWVIDYALAYA, BILASPUR (C.G.)

केंद्रीय विश्वविद्यालय अधिनियम 2009 के अंतर्गतस्थापितविश्वविद्यालय
(A Central University established by the Central Universities Act, 2009)
Phone 07752-260207, fax 07752-260154 Website www.ggu.ac.in

No/549/Engg/2013

Bilaspur. Date. 13/07/13

NOTICE INVITING QUOTATIONS

Sealed quotations are invited from contractors/reputed fabricators, manufactures forthe supply of Iron Tree Guard. Duly filled rates in should reach by speed post/registered post/courier in the office of the undersigned on or before 22/07/2013 by 3:00 PM.

S. No	Description of work	Estimated Cost	Probable no. of tree Guard	Remarks
01	Supply of Iron Tree Guard with following specification- A) 25mmX3mm thick 03 nos round patti of 20 inches dia (External) B) Welded jali spacing-35mmX35mm, dia 2mm. C) Tree Guard supported by 3 nos. vertical angle (25mmX25mmX3mm) comp. 5 ½ feet & Height of jali 4 feet. D) Painting of Tree Guard with green colour including primer.	Rs 5,00,000/-	400 nos.	

Terms and Conditions

1. Rate are inclusive of all taxes.
2. Time allowed for this work is one month.
3. Payment shall be deducted as applicable.
4. Income tax shall be deducted as applicable.
5. Quality of work as per CPWD manual.
6. The information about quotation please contact with University Engineer in office at working hours.

CC.No. 550/Engg/2013

1. PA to Registrar, for information to Registrar.
2. Finance Officer, for information.
3. Registered contractor.
4. CSIT for upload in our website.
5. Notice Board.

University Engineer
Bilaspur Date 13 / 07/13

Assistant Engineer

To,
The Registrar
Guru Ghasidas Vishwavidyalaya
Bilaspur (CG)

Sub: Your enquiry no. S.No.449/Engg/2013 Bilaspur. Date 13/07/13

Percentage rates are being given as follows:-

S. No	Description of work	Estimated Cost	Probable no. of tree Guard	Rate of each	
				Rate in figure	Rate in words
01	Supply of Iron Tree Guard with following specification- A) 25mmX3mm thick 03 nos round patti of 20 inches dia (External) B) Welded jali spacing- 35mmX35mm, dia 2mm. C) Tree Guard supported by 3 nos. vertical angle (25mmX25mmX3mm) comp. 5 ½ feet & Height of jali 4 feet. D) Painting of Tree Guard with green colour including primer.	Rs 5,00,000/-	400 nos.		

Seal and Signatures of the Firm

I/we have done myself/our self fully satisfied to read & examine the notice inviting quotation, general conditions contract, all specials conditions & specifications of work, applicable specifications, drawings, designs, applicable schedule of rates, descriptions, all the rules in respect of contract and all other contents in the notice and here by agreed for execution of the said specified work for the University Authority within the time period in accordance with that at the rate as quoted.

Dated.....

Signatures of the Firm

Postal Address:

Witness:

Address:

Occupations: