



गुरु घासीदास विश्वविद्यालय, बिलासपुर छ.ग.
GURU GHASIDAS VISHWAVIDYALAYA, BILASPUR (C.G.)
केंद्रीय विश्वविद्यालय अधिनियम 2009 के अंतर्गत स्थापित विश्वविद्यालय
(A Central University established by the Central Universities Act, 2009)
Phone 07752-260207, fax 07752-260154 Website www.ggu.ac.in

No/ 435/Engg/2012

Bilaspur. Date. 12/07/12

NOTICE INVITING QUOTATIONS

Sealed Quotations are invited from reputed firm expert in wood paneling work in computer room of MBA building of Guru Ghasidas Vishwavidyalaya. Duly filled rates in envelope (**Super scribed “quotations for enquiry no. 435/Engg/2012 dated 09/04/12”**) should reach by speed post/registered post in the office of the undersigned on or before 21/07 /2012 by 3:00 PM.

S. No.	Description of work	Estimated Cost	Time Allotted for work
1	<p>Work: Supplying and fixing 4mm Veneer ply on 6mm ply in approx. 1400 sq.ft. area over wooden frame with following specifications:</p> <p>(i) Wooden frame of sarai wood</p> <p>(ii) <u>Veneer ply</u> : ISI Mark Ecofriendly Natural Burma Teak MR Grade 4mm thick ply (size 8'X4') with low formaldehyde emission, 100% Borer proof. Branded grade premium ply quality at par with reputed brands like Greenply, Archidply, Centuaryply or equivalent.</p> <p>(iii) <u>6mm thick ply</u>: Commercial MR Grade ISI, 6mm thick Branded grade premium ply (size 8'X4') quality at par with reputed brands like Greenply, Archidply, Centuaryply or equivalent. Materials to be used during fixing work like glue and nails etc should be of standard ISI quality. Glue quality at par with reputed brands like Fevicol, jivanjor etc. and nails of Tata make or equivalent.</p>	Rs. 5,00,000/-	Two month

Terms and Conditions :-

1. Taxes/security deposit will be deducted from the bills as per rules.
2. Quality of work is to be as per CPWD manual.
3. For more details about quotations, please contact the department of Engineering in working hours.
4. The contractor will have to start the work within one week of issuance of the work order.
5. Firm is requested to visit the site before placing the quotations.

University Engineer

CC.No. 436 /Engg/2012

Bilaspur Date 12/07/12

1. PA to Registrar, for information to Registrar.
2. Finance Officer, for information.
3. Copy to HOD, CSIT for upload on Univ website.
4. EE, CPWD, Bilaspur
5. EE, Nagar Nigam, Bilaspur
6. EE, PWD, Bilaspur

Assistant Engineer

To

The Registrar

Guru Ghasidas Vishwavidyalaya

Bilaspur (C.G.)

Sub: Your enquiry no. S.NO./ 188/ Engg/2012 Bilaspur Date 09 /04/12

S.No.	Description of Item	Rate per sq.m.	
		Rate in Figures	Rate in words
1.	<p>Work: Supplying and fixing 4mm Veneer ply on 6mm ply in approx. 1400 sq.ft. area over wooden frame with following specifications:</p> <p>(i) Wooden frame of sarai wood</p> <p>(ii) <u>Veneer ply</u> : ISI Mark Ecofriendly Natural Burma Teak MR Grade 4mm thick ply (size 8'X4') with low formaldehyde emission, 100% Borer proof. Branded grade premium ply quality at par with reputed brands like Greenply, Archidply, Centuaryply or equivalent.</p> <p>(iii) <u>6mm thick ply</u>: Commercial MR Grade ISI, 6mm thick Branded grade premium ply (size 8'X4') quality at par with reputed brands like Greenply, Archidply, Centuaryply or equivalent.</p> <p>Materials to be used during fixing work like glue and nails etc should be of standard ISI quality. Glue quality at par with reputed brands like Fevicol, jivanjor etc. and nails of Tata make or equivalent.</p>		

Terms & conditions:

1. Rates are inclusive of all taxes.
2. Pan card/IT returns copy.
3. IT, CT and SD (5%) shall be deducted as applicable.
4. For more details about quotation please contact the office of UE in working hours.

Seal and Signature of the Contractor