



गुरु घासीदासविश्वविद्यालय, बिलासपुर छ.ग.
GURU GHASIDAS VISHWAVIDYALAYA, BILASPUR (C.G.)

केंद्रीय विश्वविद्यालय अधिनियम 2009 के अंतर्गतस्थापितविश्वविद्यालय
(A Central University established by the Central Universities Act, 2009)
Phone 07752-260207, fax 07752-260154 Website www.ggu.ac.in

No/ 753 /Engg/2014

Bilaspur. Date. 12 / 09 /2014

NOTICE INVITING QUOTATIONS

Sealed quotations are invited from contractors/dealers, manufactures by speed post/registered post only for the RCC Hume pipe culvert staff qtr. .The sealed quotation will be received in the office of undersigned by 04:00 PM on 19 / 09 /2014 and opened at 05:00 PM on the same day.

S. No.	Peticuler	Estimated Cost
01	RCC Hume pipe culvert staff qtr.	Rs 4.40 Lakh
Note	Scheduled item for civil works will be taken from SOR. 2010 road & SOR 2009 Building	

Terms and Conditions

1. Rate are inclusive of all taxes.
2. Time allowed for this work is one month.
3. Payment shall be deducted as applicable.
4. Income tax shall be deducted as applicable.
5. Quality of work shall be as per CPWD manual.
6. The information about quotation please contact with University Engineer in office at working hours.

CC.No. 754 /Engg/2014

1. PA to Registrar, for information to Registrar.
2. Finance Officer, for information.
3. Asstt.Engg.
4. CSIT for upload in our website.
5. Notice Board.

Registrar (Active)
Bilaspur Date 12 / 09 /2014

University Engineer

To,
 The Registrar
 Guru Ghasidas Vishwavidyalaya
 Bilaspur (CG)

Sub: Your enquiry no. S.No. /Engg/2014 Bilaspur. Date / /2014

Percentage rates are being given as follows:

Scheduled item for civil works will be taken from SOR. 2010 road & SOR 2009 Building

Item No.	Details of items	Quantity	Unit	Rate	Amount
				in Rupees	in Rupees
1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
1.1.1	in all types of soil	50	cum	112.08	5604
1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	50	cum	316	15800
9.6	Providing and laying Reinforced Cement Concrete pipe NP 3 / prestressed concrete pipe. (Laying Reinforced cement concrete pipe NP3 /prestressed concrete pipe for culverts				

z

	including fixing collar with cement mortar 1:2 but excluding bedding below pipes, excavation, protection works, backfilling, concrete and masonry works in head walls and parapets .)				
B	600 mm dia	200	cum	2096	419200
Total				440604	

Note: Rate should be quoted in appropriate column.

Seal and Signatures of the Firm

I/we have done myself/our self fully satisfied to read & examine the notice inviting quotation, general conditions contract, all specials conditions & specifications of work, applicable specifications, drawings, designs, applicable schedule of rates, descriptions, all the rules in respect of contract and all other contents in the notice and here by agreed for execution of the said specified work for the University Authority within the time period in accordance with that at the rate as quoted.

In figures.....

In words.....

Percent below/at par/above of Schedule of Rates.

Dated.....

Signatures of the Firm

Postal Address:

Witness:

Address:

z

Occupations: