

गुरु घासीदासविश्वविद्यालय, बिलासपुर छ.ग. GURU GHASIDAS VISHWAVIDYALAYA. BILASPUR (C.G.)

केंद्रीय विश्वविद्यालय अधिनियम 2009 के अंतर्गतस्थापितविश्वविद्यालय (A Central University established by the Central Universities Act, 2009)
Phone 07752-260207, fax 07752-260154 Website www.ggu.ac.in

No/ 739 /Engg/2014

Bilaspur. Date. 12 / 09 /2014

NOTICE INVITING QUOTATIONS

Sealed quotations are invited from contractors/dealers, manufactures by speed post/registered post only for the M B A in water proofing work. The sealed quotation will be received in the office of undersigned by 04:00 PM on 19 / 09 /2014 and opened at 05:00 PM on the same day.

S.	Particuler	Estimated Cost	
No.			
01	MBA in water proofing work	Rs 3.84 Lakh	
Note	Seheduled item for civil works will be taken from DSR. 2007		

Terms and Conditions

- 1. Rate are inclusive of all taxes.
- 2. Time allowed for this work is one month.
- 3. Payment shall be deducted as applicable.
- 4. Income tax shall be deducted as applicable.
- 5. Quality of work shall be as per CPWD manual.
- 6. The information about quotation please contact with University Engineer in office at working hours.

Registrar (Active) Bilaspur Date 12 / 09 /2014

CC.No. 740/Engg/2014

- 1. PA to Registrar, for information to Registrar.
- 2. Finance Officer, for information.
- 3. Asstt.Engg.
- 4. CSIT for upload in our website.
- 5. Notice Board.

University Engineer

To,

The Registrar Guru Ghasidas Vishwavidyalaya Bilaspur (CG)

Sub: Your enquiry no. S.No. /Engg/2014 Bilaspur. Date / /2014

Percentage rates are being given as follows:

Seheduled item for civil works will be taken from DSR. 2007

Item No	D.S.R ITEM NO	Item Discribtion	QTY	UNIT	RATE	Amount
1	22.6	Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying: a) after surface preparation, first layer of slurry of cement @ 0.488 kg/sum mixed with water proofing cement compound @ 0.253 kg/sum. b) laying second layer of Fibre glass cloth when the first layer is still green. Overlaps of joints of fibre cloth should not be less than 10 cm. c) third layer of 1.5 mm thickness consisting of slurry of cement @ 1.289 kg/sum mixed with water proofing cement compound @ 0.670 kg/sum and coarse sand @ 1.289 kg/sum. This will be allowed to air cure for 4 hours followed by water curing for 48 hours. The	720.00	sqm	237.00	170640.00

Z	ן	1				
		entire treatment will be taken upto 30cm on parapet wall and tucked into groove in parapet all around. d) fourth and final layer of brick tiling with cement mortar (which will be paid for separately For the purpose of measurement the entire treated surface will be measured.				
2	4.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. upto floor five level, excluding the cost of centring, shuttering and finishing:				
	4.2.2	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	50.00	cum	3951.45	197573.00
3	12.41	Providing and fixing on wall face Unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes				
	12.41.1	75 mm diameter	74.40	mtr.	95.00	7068

				Т	otal	383451.00
12	2.41.2	110 mm diameter	50.00	metre	163.40	8170.00

Note: Rate should be quoted in appropriate column.

Seal and Signatures of the Firm

I/we have done myself/our self fully satisfied to read & examine the notice inviting quotation, general conditions contract, all specials conditions & specifications of work, applicable specifications, drawings, designs, applicable schedule of rates, descriptions, all the rules in respect of contract and all other contents in the notice and here by agreed for execution of the said specified work for the University Authority within the time period in accordance with that at the rate as quoted.

n figures						
n words						
Percent below/at	par/above of Delhi Schedule of Rates.					
Dated		Signatures of the Firm				
Postal Address:						
Witness:						
Address:						
Occupations:						