



गुरु घासीदासविश्वविद्यालय, बिलासपुर छ.ग.
GURU GHASIDAS VISHWAVIDYALAYA, BILASPUR (C.G.)

केंद्रीय विश्वविद्यालय अधिनियम 2009 के अंतर्गतस्थापितविश्वविद्यालय
(A Central University established by the Central Universities Act, 2009)
Phone 07752-260207, fax 07752-260154 Website www.ggu.ac.in

No/ 749 /Engg/2014

Bilaspur. Date. 12 / 09 /2014

NOTICE INVITING QUOTATIONS

Sealed quotations are invited from contractors/dealers, manufactures by speed post/registered post only for the Staff qtr. Garage Type-2 devlopment work.The sealed quotation will be received in the office of undersigned by 04:00 PM on 19 / 09 /2014 and opened at 05:00 PM on the same day.

S. No.	Perticuler	Estimated Cost
01	Staff qtr. Garage Type-2 devlopment work	Rs 4.31 Lakh
Note	Seheduled item for civil works will be taken from SOR.2009/10	

Terms and Conditions

1. Rate are inclusive of all taxes.
2. Time allowed for this work is one month.
3. Payment shall be deducted as applicable.
4. Income tax shall be deducted as applicable.
5. Quality of work shall be as per CPWD manual.
6. The information about quotation please contact with University Engineer in office at working hours.

CC.No. 750 /Engg/2014

1. PA to Registrar, for information to Registrar.
2. Finance Officer, for information.
3. Asstt.Engg.
4. CSIT for upload in our website.
5. Notice Board.

Registrar (Active)
Bilaspur Date 12 / 09 /2014

University Engineer

To,

The Registrar
Guru Ghasidas Vishwavidyalaya
Bilaspur (CG)

Sub: Your enquiry no. S.No. /Engg/2014 Bilaspur. Date / /2014

Percentage rates are being given as follows:

Scheduled item for civil works will be taken from SOR. 2009/10

Item No.	Details of items	Quantity	Unit	Rate	Amount
				in Rupees	in Rupees
1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
1.1.1	in all types of soil	210.00	cum	112.1	23537
1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	210.000	cum	316	66360
3.1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size).	35	cum	2310.85	80879.8

z

12.58	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm				
12.58.2	Coloured pigment precast interlock concrete blocks	450	Sqm	580	261000
Total				431776.55	

Note: Rate should be quoted in appropriate column.

Seal and Signatures of the Firm

I/we have done myself/our self fully satisfied to read & examine the notice inviting quotation, general conditions contract, all specials conditions & specifications of work, applicable specifications, drawings, designs, applicable schedule of rates, descriptions, all the rules in respect of contract and all other contents in the notice and here by agreed for execution of the said specified work for the University Authority within the time period in accordance with that at the rate as quoted.

In figures.....

In words.....

Percent below/at par/above of Schedule of Rates.

Dated.....

Signatures of the Firm

Postal Address:

Witness:

Address:

Occupations: